

॥ ओम् ॥



D. A. V. PUBLIC SCHOOL

Kochas, Post-Kochas, Distt.- Rohtas(Bihar)PIN-821112

Ph.:7870326525

E-Mail Id: davkochas2013@gmail.com

दयानन्द ंगलो - वैदिक कॉलेज प्रबन्धकर्तु सडडतल, नई दल्लु दुरल संचललत सह शलकुषण संसुथलन डी० ए० वी० = जलन + वलरलन

Co-Educational, English Medium School Based On 10+2 Pattern & Syllabus of C.B.S.E. New Delhi.

PF Code No.1014 • Pension Code BRPAT- 1047516000 • School Code: BR-070

Ref. No.

Date 18.08.2018

TENDER NOTICE

Sealed quotations are invited from desirable parties through registered post for the construction of school boundary wall with entrance gate, guard room, waiting room for DAV Public School, Kochas (Rohtas)

Work should be as per specification fixed by architecture & DAV CMC Building Committee.

Quotation showing lowest rate for school boundary (Length 1895ft., Height 7 ft with 3 ft fencing of barbed wire, App. Area of wall is 13265 sq ft.) would be awarded.

The specification laid down by DAV CMC is subject to change if any, the party will be liable to follow the same.

The school keeps its right reserved to cancel the tender any time. Last date of filling the tender is within the seven days of the publishing of Tender Notice.

Specifications and other details are available on website

www.davsasaram.com

By the order of the Head of the School
in Consultation with Building Sub-Committee.

Head Office: D.A.V. College Managing Committee, Chitragupta Road, New Delhi-55 Ph. : 011-23515951, Website: www.davcmc.net.in

Regional Office: Regional Director, D.A.V. Public Schools Bihar Zone-B, C/o D.A.V. Public School, Cantt Area, Gaya(BR)-823 001, Ph.:0631-2224514

E Mail: rdbiharzonegaya@gmail.com

M/S HAPPY AND ASSOCIATES

ARCHITECTS, ENGINEERS, INTERIOR DESIGNERS

Add - 1st floor, Lalit Bhawan, Opp Dhoop Factory, New Godown, Gaya - 823001 (Bihar)

Mob. No. 7739269750, 09776824147 / Email : happyandassociates@gmail.com, sinha.prashant100@gmail.com

Ref no DAV/HA-26

Date 25/7/2017

Abstract of cost for proposed BOUNDARY WALL, BOTH ENTRANCE GATE, GUARD ROOM & WAITING ROOM at D.A.V.PUBLIC SCHOOL - KOCHAS, BIHAR						
Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
1	2.5	Earth work in Excavation including disposal of excavated garbage upto 50 m in all kinds of soil	280.5		Cu m	
2	20.3A 1	Making 25 cm dia. Bore upto 4 metre below ground with hand Auger in ordinary soil and disposal of earth upto 50 m all complete	585.0		m	
3	2.28	Supplying and filling in plinth with Local sand including watering, ramming, consolidating and dressing complete	50.0		Cu m	
4	11.72	Providing designation 100A one brick flat soiling joints filled with local sand complete	650.0		Sq m	
5	4.1.3	Providing PCC (1:2:4) with graded Stone chips of 20 mm nominal size excluding the cost of centring and shuttering all works in Foundation all complete	33.6		Cu m	
6	5.1.2	Providing and Laying in Position RCC M20 with graded stone chips of 20 mm nominal size all works upto plinth level excluding the cost of centering, shuttering and reinforcement	206.3		Cu m	
7	6.1.12 C	Fly ash Brick work with cement mortar (1:4) in Foundation & Plinth	202.5		Cu m	
8	5.9	Centring and shuttering including strutting, propping etc and removal of form				
	5.9.6	Column	310.0		Sq m	
	5.9.6	Tie beam, Top flt	390.0		Sq m	

9	5.22	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete			
	7A	TMT - 8 mm	5800.0		Kg
	7B	TMT - 10 mm	17400.0		Kg
	7C	TMT - 12 mm	160.0		Kg
	7D	TMT - 16 mm	100.0		Kg
10	10.32.2	Providing and fixing MS Gates @ 25 Kg per Sq m with a coat of approved steel Primer all complete	200.0		Kg
11	NA	Angle fixing for Barbed wire all complete re using existing posts	172.0		Each
12	NA	Fixing 4 rows Barbed wire all complete using existing wire	555.0		m
13	13.11.4	12 mm (1.8) cement Plaster Over Inner Wall	1281.0		Sq m
14	13.13.4	20 mm (1.8) cement Plaster Over Outer Wall	1281.0		Sq m
15	13.78.1	Providing one coat of cement primer of approved brand and manufacture on wall surface all complete	2562.0		Sq m
16	13.79.1	Providing water proof cement paint of approved brand and manufacture and of required shade to give and even shade three or more coat on new work all complete	2562.0		Sq m
17	13.93.1	Painting with synthetic enamel two or more coats over Wood and Steel Work	30.0		Sq m

Total cost of - Boundary wall, Both entrance gate, Guard room, Waiting room
 say total cost = _____

Rs _____

Rate per sq ft details -	
Total length of boundary =	1895'
average per sq ft rate	$1895' (l) \times 7'(b) = 13265 \text{ sq ft}$
Both entrance gate, guard room, waiting room - average cost =	_____
average cost for boundary =	_____
cost per sq ft for boundary	_____

Rashid
 25/7/2017

HAPPY & ASSOCIATES

[Handwritten signature]

Prop.